

**MARYLAND HISTORICAL TRUST
DETERMINATION OF ELIGIBILITY FORM**

NR Eligible: yes ☐
no ☐

Property Name: The Daisy Trading Post Inventory Number: HO- 258
Address: 15948
14948 Union Chapel Road City: Woodbine Zip Code: 21797
County: Howard County USGS Topographic Map: Woodbine Quad
Owner: Nicholas L. Andris Is the property being evaluated a district? ☐ yes
Tax Parcel Number: 72 Tax Map Number: 13 Tax Account ID Number: 313321
Project: Verizon - Daisy Cell Site Agency: FCC
Site visit by MHT Staff: ☐ no ☐ yes Name: _____ Date: _____
Is the property located within a historic district? ☐ yes ☒ no

If the property is within a district

District Inventory Number: _____

NR-listed district ☐ yes Eligible district ☐ yes District Name: _____

Preparer's Recommendation: Contributing resource ☐ yes ☐ no Non-contributing but eligible in another context ☐

If the property is not within a district (or the property is a district)

Preparer's Recommendation: Eligible ☒ yes ☐ no

Criteria: ☒ A ☐ B ☒ C ☐ D Considerations: ☐ A ☐ B ☐ C ☐ D ☐ E ☐ F ☐ G ☐ None

Documentation on the property/district is presented in: Maryland Inventory of Historic Properties

Description of Property and Eligibility Determination: *(Use continuation sheet if necessary and attach map and photo)*

This rural commercial structure is located on the northeast corner of Daisy and Union Chapel Roads, Howard County. Considered the earliest structure around which the town of Daisy was formed, it was constructed late in the last quarter of the nineteenth century. (Previous Survey information dates it to circa 1898.) Originally constructed to serve as a country store/market on the ground level; the second floor served as social hall and gathering place for community members.

The principal structure is a large two and one-half story frame building with a moderate sloping gabled roof. Most of the original materials are extant. They include: metal roof, wood clapboard siding (Aluminum siding described in previous survey information has been removed.), and stone foundations. Most original wood windows, (six over six double hung sash), remain in place. (Several of windows on the west facing façade, at the second floor level, have been replaced with one over one double hung, aluminum sash.) Original doors and screen doors seem to be extant. The centrally located attic window at the gable end, is a more decorative two over two, double hung sash in wood and remains in fair condition. The historic signage is now missing. There are ghosts of the markings: "Daisy Trading Post" along the front and westward side façades.

The shed additions cited and described in the existing survey form are extant. Generally the condition of the property has deteriorated in recent years but it seems stable and its vernacular architectural integrity is still very much intact.

MARYLAND HISTORICAL TRUST REVIEW

Eligibility recommended ☒ Eligibility not recommended ☐

Criteria: ☒ A ☐ B ☒ C ☐ D Considerations: ☐ A ☐ B ☐ C ☐ D ☐ E ☐ F ☐ G ☐ None

Comments: An outstanding example of its type.

[Signature]
Reviewer, Office of Preservation Services

12/2/02

Date

[Signature]
Reviewer, NR Program

11/25/02


Date

**MARYLAND HISTORICAL TRUST
NR-ELIBILITY REVIEW FORM**Continuation Sheet No. 1

The architecture, distinctive as a rural commercial structure, coupled with its central role in the life of residents of the rural village of Daisy, encourages its eligibility for the National Register under Criterion A and C.

Prepared by: Kate Mahood
Architectural Historian

Date Prepared: October 7, 2002



THE DAISY TRADING POST, ¹⁵⁹⁴⁸~~14948~~ UNION CHAPEL ROAD.
 HOWARD COUNTY, MARYLAND

HO-258



THE DAISY TRADING POST

15948 UNION CHAPEL RD

DAISY, HO. CO., MD

HO-258

October 2002

MD SHRP

VIEW LOOKING NORTH

PHOTO 1 OF 4

KARE MAHOD



THE DAISY TRADING POST
15948 UNION CHAPEL RD
DAISY, HO. CO., MD

HO-258

October 2002
MD SHPO
VIEW LOOKING N.W.
Photo # 2 of 4
KATE MAHOD



THE DAISY TRADING POST
15948 UNION CHAPEL RD
DAISY, HO. CO., MD

HO-258

October 2002
MDSHPC
VIEW LOOKING NORTH
PHOTO # 3 of 4
KATE WAHOO



THE DAISY TRADING POST
15948 UNION CHAPEL RD
DAISY, HO. CO., MD

HO-258

October 2002

1110SHD

VIEW LOOKING N.E.

PHOTO # 4 of 4

KATE MAHEED

HO-258

Norman Mullinix House, Daisy

15910 Union Chapel Road, Woodbine

Jennifer K. Cosham

April 21, 2004

Digital color photo on file at MHT



HO-258

Norman Mullinix House, Daisy

15910 Union Chapel Road, Woodbine

Jennifer K. Cosham

April 21, 2004

Digital color photo on file at MHT



HO-258

The Daisy Trading Post
Daisy
Private

Circa 1898

The Daisy Trading Post faces south on the northeast corner of Daisy and Union Chapel Roads. It is a three bay wide, three bay deep, two story high, gable roof (running north-south), frame clapboard (covered with aluminum siding) building, resting on a stone foundation, with one room on each floor and a central, square brick chimney on the north wall. The double rectangular entrance is in the south end wall, sheltered by a two story high, shed roof, open porch, held by three iron posts and one wooden post, with a large sign across the first floor reading, "Daisy Trading Post", and a smaller sign on the second floor reading, "Antiques." A one story high, shed roofed, frame addition rests along the east and west walls of the building, adding space for storage on the west, while a former truck and wagon garage on the east is now used for acid baths for stripping old paint from "antiques." A further, two story high, shed roofed addition runs along the north wall. Windows are rectangular with double hung sashes, holding six-over-six lights, except for the attic window in the gable end wall, which is a Roman arched, double-hung window, holding two-over-two lights.

The Daisy Trading Post at Daisy, Howard County, Maryland is the earliest commercial building standing at this cross roads intersection, known as Daisy, which, by its construction, was responsible for the development of Daisy as a community. Distinction attaching from age is expanded upon by its construction for use as a store, which served as a social focal point in the community, providing a community hall on its second floor, and a meeting place for the neighborhood. Additionally, the pattern of enlargement by increments over a period of time is significant for two reasons: It reflects a common practice in the building history of the United States, and it mirrors the evolution of this particular community from the late nineteenth century to today.

MARYLAND HISTORICAL TRUST

HO-258

Woodbine Quad

District 4

INVENTORY FORM FOR STATE HISTORIC SITES SURVEY MAGI# 1402585611

1 NAME

HISTORIC

Daisy Trading Post and House

AND/OR COMMON

2 LOCATION

STREET & NUMBER

(N.E. Corner Union Chapel Rd.
& Rt. #96)

15948 Union Chapel Road

CITY, TOWN

Woodbine

VICINITY OF

CONGRESSIONAL DISTRICT

6th

STATE

Maryland

COUNTY

Howard

3 CLASSIFICATION

CATEGORY

☐ DISTRICT☒ BUILDING(S)☐ STRUCTURE☐ SITE☐ OBJECT

OWNERSHIP

☐ PUBLIC☒ PRIVATE☐ BOTH

PUBLIC ACQUISITION

☐ IN PROCESS☐ BEING CONSIDERED

STATUS

☒ OCCUPIED☐ UNOCCUPIED☐ WORK IN PROGRESS

ACCESSIBLE

☒ YES: RESTRICTED☐ YES: UNRESTRICTED☐ NO

PRESENT USE

☐ AGRICULTURE☐ MUSEUM☒ COMMERCIAL☐ PARK☐ EDUCATIONAL☐ PRIVATE RESIDENCE☐ ENTERTAINMENT☐ RELIGIOUS☐ GOVERNMENT☐ SCIENTIFIC☐ INDUSTRIAL☐ TRANSPORTATION☐ MILITARY☐ OTHER:**4 OWNER OF PROPERTY**

NAME

Mr. and Mrs. Charles Raley

Telephone #:

STREET & NUMBER

15948 Union Chapel Road

CITY, TOWN

Woodbine, Maryland

VICINITY OF

STATE, zip code

21797

5 LOCATION OF LEGAL DESCRIPTION

COURTHOUSE, Tax Map 13 p. 72

REGISTRY OF DEEDS, ETC. Hall of Records

Liber #: 505

Folio #: 789

STREET & NUMBER

Howard County Court House

CITY, TOWN

Ellicott City

STATE

Maryland

6 REPRESENTATION IN EXISTING SURVEYS

TITLE

Howard County Historic Sites Inventory

DATE

1978-1979

☐ FEDERAL ☒ STATE ☐ COUNTY ☐ LOCALDEPOSITORY FOR
SURVEY RECORDS

Maryland Historical Trust

CITY, TOWN

21 State Circle, Annapolis

STATE

Maryland

7 DESCRIPTION

CONDITION

☒ EXCELLENT ☐ DETERIORATED
☐ GOOD ☐ RUINS
☐ FAIR ☐ UNEXPOSED

CHECK ONE

☒ UNALTERED
☐ ALTERED

CHECK ONE

☒ ORIGINAL SITE
☐ MOVED DATE _____

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

The Daisy Trading Post faces south on the northeast corner of Daisy and Union Chapel Roads. It is a three bay wide, three bay deep, two story high, gable roof (running north-south), frame clapboard (covered with aluminum siding) building, resting on a stone foundation, with one room on each floor and a central, square brick chimney on the north wall. The double rectangular entrance is in the south end wall, sheltered by a two story high, shed roof, open porch, held by three iron posts and one wooden post, with a large sign across the first floor reading, "Daisy Trading Post", and a smaller sign on the second floor reading, "Antiques." A one story high, shed roofed, frame addition rests along the east and west walls of the building, adding space for storage on the west, while a former truck and wagon garage on the east is now used for acid baths for stripping old paint from "antiques." A further, two story high, shed roofed addition runs along the north wall. Windows are rectangular with double hung sashes, holding six-over-six lights, except for the attic window in the gable end wall, which is a Roman arched, double-hung window, holding two-over-two lights.

The gable roof cornice is wide, with returns.

CONTINUE ON SEPARATE SHEET IF NECESSARY

8 SIGNIFICANCE

HO-258
Woodbine Quad
District 4

PERIOD	AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW			
—PREHISTORIC	—ARCHEOLOGY-PREHISTORIC	<input checked="" type="checkbox"/> COMMUNITY PLANNING	—LANDSCAPE ARCHITECTURE	—RELIGION
—1400-1499	<input checked="" type="checkbox"/> ARCHEOLOGY-HISTORIC	—CONSERVATION	—LAW	—SCIENCE
—1500-1599	—AGRICULTURE	—ECONOMICS	—LITERATURE	—SCULPTURE
—1600-1699	<input checked="" type="checkbox"/> ARCHITECTURE	—EDUCATION	—MILITARY	—SOCIAL/HUMANITARIAN
—1700-1799	—ART	—ENGINEERING	—MUSIC	—THEATER
<input checked="" type="checkbox"/> 1800-1899	<input checked="" type="checkbox"/> COMMERCE	—EXPLORATION/SETTLEMENT	—PHILOSOPHY	—TRANSPORTATION
—1900-	—COMMUNICATIONS	—INDUSTRY	—POLITICS/GOVERNMENT	—OTHER (SPECIFY)
		—INVENTION		

SPECIFIC DATES circa 1898

BUILDER/ARCHITECT

STATEMENT OF SIGNIFICANCE

The Daisy Trading Post at Daisy, Howard County, Maryland, is the earliest commercial building standing at this cross roads intersection, known as Daisy, which, by its construction, was responsible for the development of Daisy as a community.¹ Distinction attaching from age is expanded upon by its construction for use as a store, which served as a social focal point in the community, providing a community hall on its second floor, and a meeting place for the neighborhood.² Additionally, the pattern of enlargement by increments over a period of time is significant for two reasons: it reflects a common practice in the building history of the United States,³ and it mirrors the evolution of this particular community from the late nineteenth century to today.⁴

History and Support

1. Daisy did not come into being until after 1898. The 1878 Hopkins Atlas indicates no community of Daisy at the crossroads of Union Chapel Road and Daisy Road, but a farm of 92 acres owned by W. T. Silance. He and Richard Dorsey sold one acre of land for \$40.00 to John W. Ward and nine years later thirty (30) square perches of land for \$7.50. It is believed that John Ward constructed the Daisy Trading Post, named after Daisy Johnson, who was the sister of U. S. Senator Gorman of Howard County. It is believed that the front of the house was also constructed at that time with later additions made in 1893 when the 30 square perches of additional, undeveloped land were acquired by Mr. John W. Ward. On September 1, 1898 Mr. John W. Ward and his wife, Sarah, sold the general store to George W. Ward for \$1,750. It changed hands four times between 1898 and 1919 until it was finally acquired by Norman Mullinix, son of A. E. Mullinix, for whom A. E. Mullinix Road was named. Norman Mullinix operated the Daisy Trading Post successfully for fifty years. Initially a general store which sold fresh produce, yard goods, shoes and hardware, it was expanded to also furnish seed and fertilizer from Southern States.

2. It is not only important as a General Store but also as a social focal point for this section of Howard County. On Saturday nights six or seven clerks were needed to man the store, while parking places were difficult to find. Daisy, which consisted of a school and the Trading Post bustled with activity with the General Store serving not only the commercial needs of the community, but as its meeting place as well. With

CONTINUE ON SEPARATE SHEET IF NECESSARY

the formation of the International Order of Good Templers, which later became known as the I.O.O.F., the second floor was used as a social hall until 1915, when The Daisy I.O.O.F. building across the street was constructed.

3. The pattern of its enlargement by increments over a period of time is significant. The successful growth of a business, sale to a person who sought to enlarge the business, use as a social hall, and changes in the commercial use of the building are all among the reasons for the alteration and extension of existing buildings. It has been a common practice to add rooms, construct shed roofed lean toos and then to enclose them. the Daisy Trading Post typifies this practice, with frame additions. Initially it was only a one room store with hall above. Circa 1920 the shed roofed area at the end of the building was constructed to provide additional space for seed and fertilizer. Later a shed on the east side of the building was constructed as a garage for the owner's trucks and today this has been enclosed to provide an area for stripping paint from old furniture. The south facade, with all this, remains relatively unchanged, maintaining its original door and window placement.

4. John W. Ward held land in the Daisy area. As the builder of the Daisy Trading Post, he chartered a course from a rural farm economy to the growing importance of town life. The Ward family helped establish a true town center in this community by constructing first the Daisy Trading Post and later in 1915 selling .306 acres of land for \$150.00 for the construcion of the I.O.O.F. Building. A school was also constructed around this time. In 1919 Norman Mullinix acquired the property and with his brother A. Robey Mullinix developed the area still further, when in 1924 they began the operation of Mullinix Motors, located on the northwest corner of Daisy Road and Ed Warfield Road. The house next to the Daisy Trading Post was used as a residence for Norman Mullinix until 1969. Originally the school house, which now houses the Eyre Bus Service, lay east, with the I.O.O.F. building across the street. As today's zoned commercial use in the middle of a rural area, and as a property which has just acquired new ownership, the Daisy Trading Post will once again be pressed into providing the needed commercial services for this area.

9 MAJOR BIBLIOGRAPHICAL REFERENCES

MHT Worksheet - Jean S. Ewing 1972

Interview with Mrs. Marie Glennan, sister of A. Robey Mullinix,
owner, on May 21, 1980.

CONTINUE ON SEPARATE SHEET IF NECESSARY

10 GEOGRAPHICAL DATA

ACREAGE OF NOMINATED PROPERTY 1.25 Acres

Please see Attachment 1, Tax Map 13

VERBAL BOUNDARY DESCRIPTION

Please see Howard County Land Records, Liber 505 Folio 789

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE Maryland COUNTY Howard

STATE _____ COUNTY _____

11 FORM PREPARED BY

NAME / TITLE

Cleora Barnes Thompson, Archivist

ORGANIZATION

Office of Planning & Zoning-Comprehensive Planning Section

DATE

STREET & NUMBER

3450 Court House Drive

TELEPHONE

CITY OR TOWN

Ellicott City

STATE

Maryland

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 Supplement.

The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

RETURN TO: Maryland Historical Trust
The Shaw House, 21 State Circle
Annapolis, Maryland 21401
(301) 267-1438

TITLE SEARCH

HO-258 Daisy Trading Post and House
Prepared by Cleora Thompson, A.I.C.P.

<u>DATE</u>	<u>LIBER-FOLIO</u>	<u>GRANTOR</u>	<u>GRANTEE</u>	<u>TRANSACTION</u>
9-79		Carlton J. Dingman	Charles Raley	
10-3-69	505-789	Norman Mullinix	Carlton J. Dingman, Ellen M. Dingman	Deed to P/O tract called "Ridgely's Great Park" 1 Acre and 30 square perches for 5.00
12-12-1919	106-550	William M. Mayne, Mary Shipley Mayne Clarence Mayne	Norman Mullinix, Pauline K. Mullinix	1 Acre and 30 square perches of land
11-2-1914	WWLC96-429	Joseph A. R. Eyler	William M. Mayne, Clarence Mayne	1 Acre and 30 square perches of land
12-9-1907	WWLC84-429	Alva S. Ramsburg	Joseph A. R. Eyler	1 Acre and 30 square perches of land
18-11-1905	WWLC81-221	George W. Ward, Susan Ward	Alva S. Ramsburg	1 Acre and 30 square perches for \$1,000
*1-9-1898	JHO70-190	John W. Ward, Sarah Ward	George W. Ward	1 Acre and 30 square perches for \$1,750 in 2 several lots by 2 several deeds
18-7-1893	60-417	William T. Silance, Mary e. Silance	John W. Ward	Deed to 30 square perches for \$7.50
31-10-1884	49-84	William T. Silance, Richard Dorsey	John W. Ward	Deed to 1 Acre for \$40.00
4-10-1873	33-306	Dennis P. Gaither	William T. Silance	Deed

MARYLAND HISTORICAL TRUST WORKSHEET

Ho 258
1402584511NOMINATION FORM
for the
NATIONAL REGISTER OF HISTORIC PLACES, NATIONAL PARKS SERVICE

1. NAME

COMMON:

Daisy Trading Post

AND/OR HISTORIC:

2. LOCATION

STREET AND NUMBER:

Northeast corner, Union Chapel and Daisy Roads

CITY OR TOWN:

Daisy

STATE:

Md

COUNTY:

Howard

3. CLASSIFICATION

CATEGORY (Check One)	OWNERSHIP	STATUS	ACCESSIBLE TO THE PUBLIC
<input type="checkbox"/> District <input type="checkbox"/> Site <input type="checkbox"/> Object	<input type="checkbox"/> Public <input checked="" type="checkbox"/> Private <input type="checkbox"/> Both	<input checked="" type="checkbox"/> Occupied <input type="checkbox"/> Unoccupied <input type="checkbox"/> Preservation work in progress	Yes: <input checked="" type="checkbox"/> Restricted <input type="checkbox"/> Unrestricted <input type="checkbox"/> No

PRESENT USE (Check One or More as Appropriate)

<input type="checkbox"/> Agricultural <input checked="" type="checkbox"/> Commercial <input type="checkbox"/> Educational <input type="checkbox"/> Entertainment	<input type="checkbox"/> Government <input type="checkbox"/> Industrial <input type="checkbox"/> Military <input type="checkbox"/> Museum	<input type="checkbox"/> Park <input type="checkbox"/> Private Residence <input type="checkbox"/> Religious <input type="checkbox"/> Scientific	<input type="checkbox"/> Transportation <input type="checkbox"/> Other (Specify) <i>Antiques & Refurbishing</i>	<input type="checkbox"/> Comments
---	--	--	---	-----------------------------------

4. OWNER OF PROPERTY

OWNER'S NAME:

Carlton & Ellen Dingman

STREET AND NUMBER:

Union Chapel & Daisy Roads

CITY OR TOWN:

Daisy

STATE:

Md

5. LOCATION OF LEGAL DESCRIPTION

COURTHOUSE, REGISTRY OF DEEDS, ETC.:

Clerk of the Circuit Court

STREET AND NUMBER:

Howard County Courthouse

CITY OR TOWN:

Ellicott City

STATE:

Md

Title Reference of Current Deed (Book & Pg. #):

6. REPRESENTATION IN EXISTING SURVEYS

TITLE OF SURVEY:

DATE OF SURVEY:

☐ Federal☐ State☐ County☐ Local

DEPOSITORY FOR SURVEY RECORDS:

STREET AND NUMBER:

CITY OR TOWN:

STATE:

SEE INSTRUCTIONS

7. DESCRIPTION

CONDITION	(Check One)					
	<input type="checkbox"/> Excellent	<input checked="" type="checkbox"/> Good	<input type="checkbox"/> Fair	<input type="checkbox"/> Deteriorated	<input type="checkbox"/> Ruins	<input type="checkbox"/> Unexposed
	(Check One)			(Check One)		
	<input type="checkbox"/> Altered	<input checked="" type="checkbox"/> Unaltered	<input type="checkbox"/> Moved	<input checked="" type="checkbox"/> Original Site		

DESCRIBE THE PRESENT AND ORIGINAL (if known) PHYSICAL APPEARANCE

This frame clapboard store, two and a half stories high, has one room on each floor. Oblong, entrance is in the south end wall sheltered by a one-story porch. Lean-to additions at each side add space for storage on the west, while former carriage and wagon room on the east is now used for acid baths for stripping old paint from "antiques".

3 bays by 4, windows have 6 lights on 6 except for the attic window in the gable end wall, 2 over 2, arched.

The gable roof/cornice is wide, with returns.

SEE INSTRUCTIONS

8. SIGNIFICANCE

PERIOD (Check One or More as Appropriate)

☐ Pre-Columbian☐ 16th Century☐ 18th Century☐ 20th Century☐ 15th Century☐ 17th Century☒ 19th Century

SPECIFIC DATE(S) (If Applicable and Known)

1870

AREAS OF SIGNIFICANCE (Check One or More as Appropriate)

Aboriginal

☐ Prehistoric☐ Historic☐ Agriculture☐ Architecture☐ Art☒ Commerce☐ Communications☐ Conservation☐ Education☐ Engineering☐ Industry☐ Invention☐ Landscape☐ Architecture☐ Literature☐ Military☐ Music☐ Political☐ Religion/Phi-

losophy

☐ Science☐ Sculpture☐ Social/Human-

itarian

☐ Theater☐ Transportation☐ Urban Planning☐ Other (Specify)

STATEMENT OF SIGNIFICANCE

This country cross roads store
is becoming known as an antique shop
and paint-stripping operation.

SEE INSTRUCTIONS

9. MAJOR BIBLIOGRAPHICAL REFERENCES

10. GEOGRAPHICAL DATA

LATITUDE AND LONGITUDE COORDINATES DEFINING A RECTANGLE LOCATING THE PROPERTY			O R	LATITUDE AND LONGITUDE COORDINATES DEFINING THE CENTER POINT OF A PROPERTY OF LESS THAN TEN ACRES		
CORNER	LATITUDE	LONGITUDE		LATITUDE	LONGITUDE	
	Degrees Minutes Seconds	Degrees Minutes Seconds		Degrees Minutes Seconds	Degrees Minutes Seconds	
NW	° ' "	° ' "		° ' "	° ' "	
NE	° ' "	° ' "		° ' "	° ' "	
SE	° ' "	° ' "		° ' "	° ' "	
SW	° ' "	° ' "		° ' "	° ' "	

APPROXIMATE ACREAGE OF NOMINATED PROPERTY:

Acreage Justification:

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE:		COUNTY:	
STATE:		COUNTY:	
STATE:		COUNTY:	
STATE:		COUNTY:	

11. FORM PREPARED BY

NAME AND TITLE:		JEAN S. EWING	
ORGANIZATION	MARYLAND HISTORICAL TRUST	DATE	
STREET AND NUMBER:		2525 RIVA ROAD	
CITY OR TOWN:	ANNAPOLIS	STATE:	MARYLAND

12.


State Liaison Officer Review: (Office Use Only)

Significance of this property is:

National ☐ State ☐ Local ☐

Signature _____


SEE INSTRUCTIONS



531

528

MAP NO.



Attachment 2
HO-258
Daisy Trading Post & House
U.S. Geological Survey Map
Woodbine Quadrangle

HO-258
Daisy Trading Post
15948 Union Chapel Road
Woodbine
Jennifer K. Cosham
April 21, 2004
Digital color photo on file at MHT





H0 258

3204

Daily Trading Post

882 8/13



DAISY TRADING POST

STRIPPERS Inc

FOR LEASE
B-1
COMMERCIAL
301 921 229

Name: HO-258
Daisy Trading Post
Location: 15948 Union Chapel Road
Woodbine, Maryland
Photographer: Cleora B. Thompson, A.I.C.P.
Date of Photograph: May, 1980
Negatives in possession of the Maryland Historical Trust
View: South elevation
Photographer looking: North
Photograph number: 1 of 1